

Timloc Building Products offer a wide range of preformed leaded and unleaded cavity trays to meet almost any application requirement and type of masonry. The product descriptions below provide a brief overview of the cavity tray types within the Timloc range:



### Everdry Stepped Cavity Trays

Stepped cavity tray system for multi cavity options. Variable bed thickness options available for brick/block/stone work. Leaded and unleaded options available.

### Inter-loc Horizontal Cavity Trays

Pre-formed horizontal cavity tray system for new build and existing walls. Leaded and unleaded options available.





### System 2000 Horizontal Cavity Trays

Horizontal cavity tray system suitable for new build brick/block/stone work constructions.

### System 2000E Horizontal Cavity Trays

Horizontal cavity tray system suitable for remedial work on existing brick/block/stone work constructions.




### Over Lintel Cavity Trays

For installation directly above modern steel lintels in external cavity walls.

### General Purpose Cavity Trays

For installation in various applications such as above floor beams, roof abutments and meter boxes.




### Parapet Horizontal Cavity Trays

For installation directly into the internal wall of parapet wall applications.

### Purpose Made Cavity Trays

Special made-to-measure damp proof course units for DPC applications.



### Door & Window Cavity Trays

Made-to-measure cavity tray systems for all types of door and window arches and circular windows,

### Lintel Stopends

For installation where fair-faced masonry is supported by lintels, cavity trays or combined lintels.



Use the table below to establish which Timloc Cavity Tray type is best suited to your project specification:

Cavity Tray Type ▶ Application ▼	Everdry	Inter-loc	System 2000	System 2000E	Over Lintel	General Purpose	Parapet Horizontal	Purpose Made	Door & Window	Lintel Stopend
Pitched Roof	✓									
Flat Roof		✓	✓	✓						
Lean-to		✓	✓	✓						
Mono-pitch		✓	✓	✓						
Concrete Ring Beams		✓	✓	✓		✓				
Airbricks, Ducts, Cavity Liners, Meter Boxes etc.		✓	✓	✓		✓				
Existing Walls (Remedial Work)		✓		✓						
Steel Lintels					✓					✓
Parapet Walls							✓			
DPC Applications								✓		
Door & Window Arches									✓	
Circular Windows									✓	
Leaded Options	✓	✓	✓							

## Cavity Tray Scheduling

Timloc Building Products offer a free scheduling/estimating service for our full range of products, we primarily and most frequently schedule for cavity trays as there are numerous variations of products to suit specific applications.

Our schedule format can be produced to your individual instruction i.e. specific to site, house types, blocks, plots and even area of application to give a comprehensive and accurate schedule.



### Technical | Kerry Taylor

Technical Service Manager

T: 01405 782 769

E: [technical@timloc.co.uk](mailto:technical@timloc.co.uk)

If you require further information, clarification, or to enquire about our call-off and scheduling service please get in touch with the Timloc Building Products Technical Department and we will be happy to assist.

Product datasheets are also available at: [www.timloc.co.uk](http://www.timloc.co.uk)